

Notice #2: Update 25/03/14:King / Sumach Intersection Reconstruction

In the interest of getting the previous notice out in a timely manner, ahead of the Phase 2 eastbound King Street East lane closure, contact details were mistakenly omitted from the previous notice. Contact information will be included on all future notices.

Dundee Kilmer/EllisDon Ledcor has begun the reconstruction of the King and Sumach Street intersection. This work will be carried out in two phases from late March 2014 to approximately the end of May 2014. The team will make every effort to minimize disruption to local residents and businesses and will provide regular updates to advise of ongoing and planned work in the area.

The notices will be distributed through multiple channels. The Corktown Residents and Business Association will forward updates to their membership and post on <http://corktown.ca/>. If you are not currently a member of the CRBA, please visit their website to join.

Waterfront Toronto will forward updates to the West Don Lands Construction Liaison Committee, who will share the notice with the groups represented on the committee. The notices will also be posted on Waterfront Toronto’s website at http://www.waterfronttoronto.ca/explore_projects2/west_don_lands.

Please direct inquiries related to the reconstruction of King Street East/Sumach Street reconstruction to: info@dundeekilmer.com.

Phase 1 : Underway

Work has begun and will be ongoing throughout the month of March. Phase 1 work includes the installation of manholes, catchbasins and below-grade pipes required to upgrade the underground stormwater infrastructure.

Traffic Impact: The intersection will remain open during this work. Traffic control measures will be implemented to manage the work zones. East and west traffic will be maintained on King Street, as well as north and south traffic on Sumach Street.

Phase 2 : April 7 – May 31, 2014 (Diagram Attached)

Phase 2 work includes all removal work required for the reconstruction of the intersection, including the removal of the existing concrete sidewalk, asphalt pavement, and the existing TTC tracks and concrete bases. This work is to prepare for the installation of a new concrete road base, new TTC/Street lighting poles and bases, new TTC drain system, new TTC Track system and new traffic lights at the intersection. Sidewalk repairs, asphalt paving, the installation of new crosswalks and line painting will also be completed in this phase.

Traffic Impact: A partial closure of the intersection is required to complete this phase of work. Westbound traffic will be maintained on the north side of King Street throughout the duration of construction. Access to all businesses adjacent to the intersection will be maintained.

Eastbound traffic on King Street will be rerouted during this phase of construction. Access to Sumach Street will also be impacted during this phase. Sumach Street northbound from Eastern Avenue will be open to local traffic only, and Sumach Street South of King Street will be closed to all traffic during this phase.

